

Data Center Information

Written by Web master

Wednesday, 12 May 2004 11:54 - Last Updated Tuesday, 31 March 2009 15:31

Building Size:

.....

35,000+ Sq. Ft. A new class A office building

Connection:

.....

Redundant OC-12 Loops through AT&T, SPRINT, and Qwest.

Networking:

.....

Gigabit Ethernet infrastructure.

All wiring is done with tested factory terminated Cat5e gigabit Ethernet wiring to ensure maximum bandwidth. We are a full Cisco shop, using Cisco routers, and Cisco switches

Network Security:

.....

Cisco Pix and Cisco IDS attack prevention in place.

Cooling:

.....

Redundant Rooftop 10 ½ Ton AC Units.

The server room is kept at a cool 66 degrees Fahrenheit and a proper level of humidity to ensure the equipment in the Data Center is kept at the right temperature.

UPS:

.....

Full UPS Battery Backup for all equipment.

All UPS equipment is tested once a week to ensure proper working order.

Generator:

.....

Full diesel generator backup for all equipment

All equipment is on a powerful diesel generator which automatically is turned on after 4 seconds after a power failure.